# 2021 CITY JUSTICE CENTER SECURITY UPGRADES



# CELL DOORS AND LOCKS

## **CHALLENGES**

Minimum security locks that are being compromised by the inmates. The hardware is no longer manufactured and parts are difficult to procure.



# SOLUTION

New medium/maximum security cell doors, locks, frames, hardware and glazing throughout the facility



**COST = \$7.6M** 

# DAY ROOM WINDOW PROTECTION

## **CHALLENGES**

Inmates were able to defeat the existing window screening and doors leading to the exterior windows.



## **SOLUTION**

Install new heavy duty high-security screening and doors.

**COST = \$1.3M** 

# **CONTROLS SYSTEM & OFFICER PROTECTION**

#### CHALLENGES

The operating software is proprietary, outdated and no longer supported. Portions of this systems were irreparably damaged in the recent uprisings due to the existing controls and guards being in the unprotected open day room

#### SOLUTION

New facility-wide controls system utilizing easily-obtained hardware and non-proprietary software

New elevated and protected guard control stations on the 3<sup>rd</sup> and 4<sup>th</sup> floors allowing a single guard to view and control 2 pods as well as the recreation area from a single room. The door operations can also be controlled by tablets by roaming guards outside of the new guard control station.

New protected sally-port entrance into each day room pod.

Subdivided pods to provide the officers more precise control over large populations

## COST

CONTROLS SYSTEM

\$4M

**GUARD STATIONS** 


\$3M

# **CONTROLS SYSTEM & OFFICER PROTECTION**

**CHALLENGES** 

## SOLUTION





# **FURNITURE**


### **CHALLENGES**

Existing furniture is not correction-grade and is not securely fastened to the floor. Inmates utilized the loose furniture to damage the control station, security screening, windows, etc. in the recent uprisings.



## **SOLUTION**

3rd and 4th Floors - New corrections-grade day room furniture securely fastened to the floor



 $\overline{\text{COST}} = \$600 \text{K}$ 

# LIGHTING

#### CHALLENGES

Inmates are able to damage the existing cell lighting fixtures and, in some cases, fashion weapons and/or tools. The existing day room lighting fixtures hang low allowing inmates to strike them with objects creating debris that could also be fashioned into weapons/tools.



#### SOLUTION

New super-maximum security level cell and day room lighting. The day room lighting will be hung much higher and secured with aviation cable to prevent them from being

dislodged.

#### Correctional Lighting Best Practices

#### Lighting Levels, Materials & Gauges

Kenall fixtures meet or exceed every security requirement for their intended application. Whether a minimum, medium, maximum, or super-maximum application, our fixtures are engineered to resist everything from the most violent abuse to the cleverest attempts at tampering and concealment.

Material Selection Guidelines				
	Minimum			
Housing Gauge, Steel	18	16	14	12
Housing Gauge, Stainless Steel	20	18	16	14
Inner Lens	.125"	.125"	.125"	.125"
Outer Lens-Polycarbonate	.187"	250"	.375"	500"
Outer Lens -Tempered Glass	.250"	.375"	.500"	.750"
Fasteners	TP (Tamper-proof)	Recessed TP	Recessed TP	Recessed TP

**COST = \$1.9M** 

# FIRE ALARM SYSTEM

#### **CHALLENGES**

The existing fire alarm system is the original system installed during the construction of the facility in the early 2000's and is in need of a comprehensive diagnostic testing and upgrades.

### **SOLUTION**

A comprehensive diagnostic testing, firmware upgrade, software upgrade, and testing/replacement of all heat detectors (15 in total), smoke detectors (253 in total), and HVAC system duct (smoke) detectors (154 in total) that fall outside maximum functionality status. The master control panel, remote panels controlling horn/strobe activation, and existing annunciator panels will be fully checked for full functionality and any components falling outside specifications will be replaced. All wiring will be checked for ground fault condition.



Plus \$110K per year for testing and device cleaning

# COST SUMMARY

CELL DOORS AND LOCKS \$7,600,000

DAY ROOM WINDOW PROTECTION \$1,300,000

CONTROLS SYSTEM & OFFICER \$7,000,000 (not including the sally-port entrance and

PROTECTION day room subdivision)

FURNITURE \$600,000

LIGHTING \$1,900,000

FIRE ALARM \$500,000

DESIGN FEES \$600,000

TOTAL PROJECT COST \$19,500,000

\*\* Scheduled to be completed by Q2 2023 \*\*