

**LACLEDE'S LANDING STREETScape IMPROVEMENTS  
FIRST AND SECOND STREETS  
Federal Project Number: STP-5401(554)**

**ADDENDUM #3 TO BID DOCUMENTS  
Issuance Date: December 18, 2012**

**Bid Opening Date: December 21, 2012**

**Changes and Clarifications to Drawings C17 and C19:**

Drawings C17 and C19 each show the construction of a new concrete entrance apron at approximate station 1+00. These two entrance ramps shall be constructed of 7 inches of non-reinforced PCC over 4 inches of  $\frac{3}{4}$  inch minus compacted stone base meeting the specifications of JSP 9.

**Changes to Itemized Bid Form:**

To accommodate the payment of the new entrance ramp construction, the Itemized Bid Form has been revised with the addition of a new payment item "***Concrete Entrance Apron (7'') over Aggregate Base (4'')***". The revised bid form is provided as Attachment A.

(The demolition of the existing ramps is shown on Drawings C7 and C9. Payment for their demolition will be made under payment item "Excavation/Demolition and Haul Off from Bldg face to Bldg face").

**ITEMIZED BID FORM**

<b>Laclede's Landing Streetscape</b> Date: December 18, 2012 State: Missouri Municipality: City of St. Louis		<u>Base Bid</u> - 2nd Street from Washington to Morgan				<u>Bid Alt A</u> - 1st Street from 0+25.00 to 2+08.94				<u>Bid Alt B</u> - 1st Street from 2+08.94 to 2+56.21				<u>Bid Alt C</u> - 1st Street from 2+56.21 to 4+99.58				<u>Bid Alt D</u> - 1st Street from 4+99.58 to 5+63.05			
		UNIT	ESTIMATED QUANTITY	UNIT PRICE	TOTAL COST	UNIT	ESTIMATED QUANTITY	UNIT PRICE	TOTAL COST	UNIT	ESTIMATED QUANTITY	UNIT PRICE	TOTAL COST	UNIT	ESTIMATED QUANTITY	UNIT PRICE	TOTAL COST	UNIT	ESTIMATED QUANTITY	UNIT PRICE	TOTAL COST
1	Brick Paver Sidewalk - Removal, partial Storage for re-use / disposal of remainder	SF	12,961			SF	1,310			SF	566			SF	5,780			SF	1,593		
2	Metal Sidewalk Street Sign Plaque - Removal, Storage and re-install	EACH	13			EACH	0			EACH	6			EACH	0			EACH	6		
3	Canopy w/ Poles - Removal, Storage and re-install	EACH	2			EACH	0														
4	Flag Pole - Removal, Storage and re-install	EACH	3			EACH	0			EACH	0			EACH	2			EACH	0		
5	Bench - Removal Storage and Re-install	EACH	9			EACH	0			EACH	0			EACH	4			EACH	2		
6	Trash Can -Removal, Storage and re-install	EACH	4			EACH	1			EACH	0			EACH	2			EACH	0		
7	Flower Pot Removal, Storage and re-install	EACH	34			EACH	3			EACH	0			EACH	14			EACH	3		
8	Newspaper Box - Removal, Storage and re-install	EACH	5			EACH	0			EACH	0			EACH	3			EACH	0		
9	Mailbox - Removal, Storage and re-install	EACH	1			EACH	0			EACH	0			EACH	1			EACH	0		
10	Information Signs -Removal, Storage and re-install	EACH	2			EACH	0			EACH	1			EACH	0			EACH	1		
11	Street Sign - Removal, Storage and re-install	EACH	7			EACH	3			EACH	2			EACH	3			EACH	3		
12	Swinging Gate at Lucas - Removal	EACH	1			EACH	0														
13	Tree Removal	EACH	6			EACH	0			EACH	0			EACH	6			EACH	1		
14	Construction Staking	L. SUM	1			L. SUM	1			L. SUM	1			L. SUM	1			L. SUM	1		
15	Cobblestone Rem., Store and Replace with 6" locking sand over 4"of 3/4" Minus	SF	9,108			SF	4,648			SF	0			SF	5,020			SF	262		
16	Aggregate Base Course for Cobblestone (18"of 1-1/2" - 2" Clean)	CY	506			CY	258			CY	0			CY	279			CY	15		
17	Excavation / Demolition and Haul Off from Bldg face to Building face	CY	1,431			CY	450			CY	151			CY	630			CY	222		
18	Geotechnical Fabric for Ground Stabilization under Cobblestone	SY	1,012			SY	516			SY	250			SY	650			SY	30		
19	Underdrain System for Cobblestone	LF	1,315			LF	573			LF	61			LF	770			LF	145		
20	Concrete Pavement (10") and Aggregate Base (8") at Lucas Intersection	SY	132			SY	0			SY	217			SY	0			SY	0		
21	Concrete Pavement (10") and Aggregate Base (8") at Morgan Intersection	SY	222			SY	0			SY	0			SY	0			SY	218		
22	Concrete Curb and Gutter (4-1/2" Tall Curb / 8" Wide Gutter)	LF	1,098			LF	370			LF	85			LF	488			LF	130		
23	Concrete Sidewalk (5") over Aggregate Base (4") with 2' wide brick paver band	SF	12,057			SF	2,638			SF	573			SF	4,635			SF	1,603		
24	Detectable Warning Device	EACH	13			EACH	2			EACH	5			EACH	0			EACH	6		
25	Deciduous Tree, 3" caliper, B&B (Japanese Zelkova)	EACH	11			EACH	0			EACH	0			EACH	9			EACH	0		
26	Deciduous Tree, 3" caliper, B&B (English Hornbeam)	EACH	4			EACH	0			EACH	0			EACH	0			EACH	2		
27	Shrub, 1 qt. (Green Velvet Boxwood)	EACH	6			EACH	0			EACH	0			EACH	0			EACH	7		

28	Ground Cover, Creeping Lilyturf, 1 qt.	EACH	729			EACH	0			EACH	0			EACH	250			EACH	0		
29	Planting Soil Mix	CY	115			CY	0			CY	0			CY	37			CY	19		
30	6', metal, backless bench	EACH	17			EACH	0			EACH	0			EACH	8			EACH	0		
31	Water Main (8") - Abandon and Replace	LF	627			LF	190			LF	110			LF	244			LF	124		
32	Water Service Lines (3/4" - 6") - Abandon and Replace	LF	205			LF	18			LF	0			LF	167			LF	0		
33	Water Lines to FH (6") - Abandon and Replace	LF	79			LF	20			LF	0			LF	10			LF	10		
34	Water Manholes - Abandon and Replace	EACH	16			EACH	0			EACH	0			EACH	4			EACH	3		
35	Water Valve - Abandon and Replace	EACH	4			EACH	0			EACH	3			EACH	4			EACH	0		
36	Water Meter - Abandon and Replace	EACH	2			EACH	2			EACH	0			EACH	8			EACH	0		
37	Fire Hydrants - Remove and Replace	EACH	6			EACH	1			EACH	0			EACH	1			EACH	1		
38	Water Division Fee	L. SUM	1	\$25,500	\$25,500	L. SUM	1	\$17,500	\$17,500	L. SUM	1	\$2,500	\$2,500	L. SUM	1	\$2,500	\$2,500	L. SUM	1	\$2,500	\$2,500
39	Street Light Removal and Replacement	EACH	16			EACH	4			EACH	0			EACH	9			EACH	0		
40	Street Light Pull Box Adjust to Grade	EACH	4			EACH	1			EACH	0			EACH	0			EACH	1		
41	Temporary Wiring for Lighting Circuits	L. SUM	1			L. SUM	1			L. SUM	0			L. SUM	1			L. SUM	0		
42	Inlet Manholes Adjust to Grade	EACH	3			EACH	0			EACH	0			EACH	0			EACH	0		
43	Sewer Manholes Adjust to Grade	EACH	3			EACH	0			EACH	1			EACH	1			EACH	0		
44	Curb Inlet (Trapped)	EACH	6			EACH	1			EACH	4			EACH	2			EACH	2		
45	Sewer Manholes	EACH	3			EACH	0			EACH	4			EACH	1			EACH	2		
46	Small Drains Adjust to Grade	EACH	4			EACH	0			EACH	0			EACH	2			EACH	0		
47	12" RCP Storm Sewers	LF	230			LF	0			LF	30			LF	67			LF	30		
48	Utility Coordination	L. SUM	1			L. SUM	1			L. SUM	1			L. SUM	1			L. SUM	1		
49	Steam Line Abandonment	L. SUM	0			L. SUM	1			L. SUM	1			L. SUM	0			L. SUM	0		
50	Mobilization	L. SUM	1			L. SUM	1			L. SUM	1			L. SUM	1			L. SUM	1		
51	"Road Closed" Type III Barricade	EACH	8			EACH	4			EACH	8			EACH	4			EACH	8		
52	"Road Closed Ahead" Type III Barricade	EACH	4			EACH	0			EACH	2			EACH	1			EACH	3		
53	"Local Traffic Only" Sign	EACH	4			EACH	0			EACH	2			EACH	1			EACH	3		
54	"Sidewalk Closed-Detour Opposite Side of Street" Sign	EACH	4			EACH	4			EACH	4			EACH	4			EACH	4		
55	"Traffic Control and Pedestrian Access"	L. SUM	1			L. SUM	1			L. SUM	1			L. SUM	1			L. SUM	1		
56	"Concrete Entrance Apron (7") over Aggregate Base (4")	SF	320			SF	380			SF	0			SF	0			SF	0		
	SUBTOTALS																				
	<b>Total for Base Bid</b>																				
	<b>Total for Base Bid + Alt. A</b>																				
	<b>Total for Base Bid + Alt. A + B</b>																				
	<b>Total for Base Bid + Alt. A + B + C</b>																				
	<b>Total for Base Bid + Alt. A + B + C + D</b>																				